

### Status of the LZ Experiment

Tomasz Biesiadzinski For the LZ Collaboration 02/19/2018

**LLWI 2018** 








### LZ Collaboration





- 1. Center for Underground Physics (South Korea)
- 2. LIP Coimbra (Portugal)
- 3. MEPhI (Russia)
- 4. Imperial College London (UK)
- 5. Royal Holloway University of London (UK)
- 6. STFC Rutherford Appleton Lab (UK)
- 7. University College London (UK)
- 8. University of Bristol (UK)
- 9. University of Edinburgh (UK)
- 10. University of Liverpool (UK)
- 11. University of Oxford (UK)
- 12. University of Sheffield (UK)
- 13. Black Hill State University (US)
- 14. Brandeis University (US)
- 15. Brookhaven National Lab (US)
- 16. Brown University (US)
- 17. Fermi National Accelerator Lab (US)
- 18. Lawrence Berkeley National Lab (US)
- 19. Lawrence Livermore National Lab (US)

- 20. Northwestern University (US)
- 21. Pennsylvania State University (US)
- 22.SLAC National Accelerator Lab (US)
- 23. South Dakota School of Mines and Technology (US)
- 24. South Dakota Science and Technology Authority (US)
- 25. Texas A&M University (US)
- 26. University at Albany (US)
- 27. University of Alabama (US)
- 28. University of California, Berkeley (US)
- 29. University of California, Davis (US)
- 30. University of California, Santa Barbara (US)
- 31.University of Maryland (US)
- 32. University of Massachusetts (US)
- 33. University of Michigan (US)
- 34. University of Rochester (US)
- 35. University of South Dakota (US)
- 36. University of Wisconsin Madison (US)
- 37. Washington University in St. Louis (US)
- 38. Yale University (US)



# Evidence For Dark Matter










# Time Projection Chamber

- LZ is a dual-phase time projection chamber (TPC)
- Particle collision → light (S1) + charge
- Charge is extracted
  - → electroluminescence (S2)
- 3D position reconstruction
  - The S2 is localized in X-Y
  - Time difference between S1 and S2 gives depth
- Strengths of Xe TPCs
  - Self-shielding + position
     reconstruction → Fiducialization
  - S2/S1 ratio → BG discrimination





### LZ

• 10 tonnes total, 7 tonnes active, 5.6 tonnes fiducial


• 1.5 m diameter, 1.5 m height

• 2-component veto system: LXe skin and outer detector

Gas circulation/purification system @ 500 slpm

Internal an external calibration, ER and NR

494 3" PMTs in TPC




10.2 kV/cm electroluminescence field (11.5kV difference)

SLAC

310 V/cm drift field (50kV Cathode)

Scintillator



Neutron Calib. Conduit




### **BG Controls**

- Screening of ALL materials
  - About 50% done
    - See https://arxiv.org/abs/1702.02646 for example of the choice of Titanium
  - Includes radon assays
- On line radon removal system for most problematic components – warm cables
- Radon-reduced clean room for TPC assembly
- Exposure to dust tracked with witness plates
- Procedures and real-time quality controls





### Discrimination and Fiducialization





# Backgrounds

SLAC

5.6 Tonne fiducial mass, 1000 live-days, ~1.5 - 6.5keV, single scatters and veto


Background Source	ERs	NRs	
Detector Components	9	0.07	
Dispersed Radionuclides — Rn, Kr, Ar	816	-	
Laboratory and Cosmogenics	5	0.06	
Surface Contamination and Dust	40	0.39	
Physics Backgrounds — 2β decay, neutrinos* * Not Including *B and hep	322	0.51	
Total (after 99.5% discrimination and 50% NR efficiency)	6	6.48	

Feb 19, 2018

LLWI 2018



# Sensitivity






# **Progress**

### Xenon Procurement and Purification



- 6.5 tonnes of Xe at SLAC
  - 4 tonnes to go
- Xenon purification via charcoal chromatography
  - https://arxiv.org/abs/1605.0 3844







## Xe & OD Vessels





- Inner and outer vessels are finished, delivery soon
- Outer detector scintillator tanks finished this month





# Xe Gas and Liquid Handling




- Circulation tests at ~70SLPM at SLAC
- LZ circulation system installed and tested underground at the end of 2018
  - Using a dummy cryostat







## **HV** Testing



- Cathode cable tested to 120kV
  - Cathode feedthrough testing in LAr to same voltage
- Small versions of grids (and individual wires) tested in gas and liquid Xe
- Full scale testing coming








Feb 19, 2018



### HV: Full Scale Grids





 50cm test grid woven and glued to test methods



Prototype Bottom Grid

• First full scale grid in production now



## PMT & DAQ



- All 3" PMTs in hand
- All cold tested
- DAQ chain test constructed
- Measured response to Xe scintillation light
  - https://arxiv.org/abs/1801.01597





### Schedule



- CD1 Review March 2015
- CD2 Review April 2016
- CD3 Review February 2017 construction can start in earnest
- Cryostat fabrication just completed
- PMT array assembly begins in March
- Xenon handling installation and commissioning starts Fall 2018
- TPC installation Spring-Summer 2019
- Cooldown starts Winter 2019-2020
- First physics data Spring 2020



### Conclusions



- WIMP dark matter remains an attractive dark matter candidate
- LZ will exclude a large fraction of the available parameter space and has the potential to discover WIMPs even if previous experiments fail to see them
- Massive screening and R&D program has made LZ possible
- Construction is under way!
- Details in the technical design report https://arxiv.org/abs/1703.09144
- ... and the sensitivity paper: https://arxiv.org/abs/1802.06039

Thank You