



NATIONAL  
ACCELERATOR  
LABORATORY



# First Results From the LZ system Test Platform @ SLAC

Tomasz Biesiadzinski  
For the LZ Collaboration  
02/19/2016

UCLA Dark Matter 2016



*32 Institutions  
About 200 people*

# LZ = LUX + ZEPLIN

Center for Underground Physics (Korea)  
LIP Coimbra (Portugal)  
MEPhI (Russia)  
Edinburgh University (UK)  
University of Liverpool (UK)  
Imperial College London (UK)  
University College London (UK)  
University of Oxford (UK)  
STFC Rutherford Appleton Laboratories (UK)  
University of Sheffield (UK)

University of Alabama  
University at Albany SUNY  
Berkeley Lab (LBNL)  
University of California, Berkeley  
Brookhaven National Laboratory  
Brown University  
University of California, Davis  
Fermi National Accelerator Laboratory  
Lawrence Livermore National Laboratory  
University of Maryland  
University of Michigan  
Northwestern University  
University of Rochester  
University of California, Santa Barbara  
University of South Dakota  
South Dakota School of Mines & Technology  
South Dakota Science and Technology Authority  
SLAC National Accelerator Laboratory  
Texas A&M  
Washington University  
University of Wisconsin  
Yale University

# LZ Testing Program...

- ... is very extensive
- LZ systems and components development and Xe TPC research at many institutions
  - Small chamber Xe tests at Imperial, LBNL, LLNL, LIP Coimbra, U. Of Michigan, UC Berkeley, UC Davis, MEPHI
    - Testing of electrical characteristics of wires and small grids, PTFE and wire reflectivity, purity monitoring,
    - Research into S2 generation, energy resolution, yields and more!
  - PMT testing (Brown)
  - Cathode HV feedthrough performance in liquid Ar (LBNL)
  - Many more!
- SLAC system test platform

# SLAC Test Platform Infrastructure

TS  
Dewar

Sampling  
System

Gas Panel

Vessel  
Breakout

TS  
Panel

Vessel  
Breakout

Detector

Purification  
Tower

Cath. HV

- 2 floors (the “hut”) within the former BaBar hall
- Circulation pump housed in a separate building

# Phase 1

- Main goals:
  - High voltage tests of components
  - Purification system tests
- Ancillary LZ systems tested along the way
  - Sensors, slow control + PLC



Vacuum Can

Xe Can

TPC



Cathode HV Feedthrough

Grid



# High Voltage Tests

- Cathode Voltage
  - Previous LXe experiments reached only  $\sim 10\text{kV}$  on cathode
- Anode-gate extraction field
  - validation of the design S2 region
- Avoid single photon and electron generation
  - Ex: E. Aprile, et al., *Astroparticle Physics*, 35, (2012), 573




- SLAC LZ system test
  - Surface fields match LZ
  - Measure light/charge vs voltage, purity, wire treatment, etc

# Purification

- Vaporize → purify → re-condense
- Circulation
  - Testing LZ design: circulation compressor (Wisconsin + others) + gas system
- Purification at high flow rates
  - LZ – like purification tower
    - dual and single phase heat exchanges, weir reservoir, condenser/sub-cooler, liquid valves (coming soon)
  - SAES Getter – should handle over 100L/min
  - Purity measurement
    - TPC with half meter drift length (LBNL + SLAC)
    - ppt (volatiles) sampling system (Maryland)
    - source injection coming soon (LBNL + SLAC)
    - Purity monitor coming soon (UC Davis)



# First (Simplified) Run Of Phase 1



Testing the region where highest voltage is applied

- One PMT (R9288) with 4 ns digitizer resolution, high and low gain channels
- Single phase, no precision level or position sensor

# Cathode- Bottom Grid Region

Inner Xe Can




View through an optical fiber during assembly - illuminated



Thanks to: Jeremy Mock  
02/19/2016

# Cathode Grid HV Performance

- 50kV requirement and 100kV goal for LZ
  - Same fields achieved at half voltage in the test platform
- Tested with multiple ramp ups
  - Test platform exceeded 50kV goal
  - Intermittent light generation observed
  - HV taken to breakdown




Hold  
Test @  
50kV


- Voltage held for over 6 hours + successfully monitored light emission
  - Single photon threshold varied between ramp ups – will improve during next run
- Long term light/charge emission will be tested soon

# Breakdown @72kV


- Breakdown believed to originate in the (non-LZ) HV feedthrough
- Non-ohmic behavior @64kV
  - disappeared after ramping down to 62kV and not seen during following ramp up



Optical fiber view of cathode HV connection. Looking from the bottom



During assembly - illuminated



During breakdown

Vessel wall



HV Connection

TPC

UCLA Dark Matter 2016


# Phase 1 in Near Future

- Full TPC installed
  - Two LZ prototype PMTs R11410-20
  - Ability to upgrade to a multi-PMT array
- New and/or improved instrumentation
  - Precision level sensors, precision position sensors, acoustic sensors, loop antenna (TAMU), RTDs
- Improvements to slow control stability and performance
- Condenser/sub-cooler added to the circulation path
- Source injection to be added in near future



# Phase 2

- Wide and short
  - 166 cm diameter, 25cm height available
- Will hold the cathode or anode-gate pair
  - Full scale grid prototyping
- Quality testing of final LZ grids
  - Upper corner of the TPC tested at full LZ voltage
  - Cathode tested to LZ field
- About 500kg of Xe needed



# Conclusion

- Extensive testing of LZ design underway
- Phase 1 system test platform provides a unique opportunity to test various components and their integration
- Phase 2 will make sure that actual LZ grids meet their goals

Thank You

# Backup


# Grids and Wires

- California fine wire SS304
- Anode:
  - 100  $\mu\text{m}$ , 2.5 mm spacing
- Gate:
  - 75  $\mu\text{m}$ , 5 mm spacing
- Cathode:
  - 100  $\mu\text{m}$  (150  $\mu\text{m}$  during past run), 5 mm spacing
- Bottom:
  - 100  $\mu\text{m}$  (slightly larger than LZ plan), 5 mm spacing

# Lessons From First Phase 1 Run: Successes and “Successful Failures”

- Detector
  - Circulation at 50L/min through detector
  - Low condensation rate, ~16 L/min of gas
  - Problems with some sensors due to wiring, handling and readout
- Slow control software and PLC successfully controlled the system
  - Allows for quick creation of custom “process” pages
  - Some stability issues
- HV!

# Consequences of Breakdown



- Comparison of RFR chain resistance across multiple voltage ramp-ups
  - Before (circles, diamonds, triangles) and after (squares) breakdown
- No change observed after breakdown → early sign that performance was not altered
  - RFR since inspected and no damage observed

# Understanding Light

## 10 Random Waveforms Plotted

